

Specification For Transformer Base Sinusoidal parallel True On Line Double Conversion UPS		
General Data		
Vendor's Name:	Average Ambient Temperature (Min/Max)	0 °c / 52 °c
Tag No.(s):	Max.Design Temperature:	+40 °c
App. Document.(s):	Max. Sun Temperature:	+75 °c
UPS & Battery Spec. Doc. No.:	Max.Relative Humidity:	90%
UPS sizing Doc. No.:	Mean Sea Level:	1500 meter
Technical Data		
General	Required	Vendor Data
1	Applicable Code & Standard	IEC 62040,IPS-M-EL-176(2)
2	Electromagnetic Compatibility	As per IEC 62040-2
3	Service	Control rooms requirement
4	Rated input	3phase,400 v ± 10%,50Hz ± 5%
5	Rated out put	110 V AC ± 1%
6	Rated Power	10 KVA
7	Country of Origin	By Vendor
8	Cold Start Facility	Required
9	No. of UPS	<input type="checkbox"/> Single <input checked="" type="checkbox"/> Double
Mechanical Characteristic		
10	Noise Level (in accordance with ISO 7779)The sound pressure level measured at 1 m (39 in) distance from the UPS	<input type="checkbox"/> < 55 dBA <input checked="" type="checkbox"/> <60dBA <input type="checkbox"/> <65dBA <input type="checkbox"/> <70dBA
11	Permissive Max. Temp.Rise	By Vendor
12	Enclosure Construction	Sheet steel with min.thickness 1.5 mm
13	degree of protection in accordance with IEC 60529	<input type="checkbox"/> IP21 <input checked="" type="checkbox"/> IP31 <input type="checkbox"/> IP42
14	Type of Cooling	<input type="checkbox"/> Natural <input checked="" type="checkbox"/> forced (n+1 Fan)
15	Dimension	MINIMUM SIZE
16	Weight	MINIMUM WEIGHT
17	Panel mounting	<input checked="" type="checkbox"/> Floor mounted <input type="checkbox"/> Wall mounted
18	Access	<input checked="" type="checkbox"/> Front access <input type="checkbox"/> Rear access
19	MTBF (at 20 °C (68 °F))	<input type="checkbox"/> ≥90,000 Hr <input checked="" type="checkbox"/> ≥140,000 Hr <input type="checkbox"/> ≥280,000 Hr
20	MTTR	<input checked="" type="checkbox"/> ≤1 Hr <input type="checkbox"/> ≤2 Hr <input type="checkbox"/> ≤4 Hr
21	Finish Color	RAL 7032
Load Characteristics		
22	Load consumption	10 KVA 8 KW
23	Load description	Instrument,PLC,DCS,Work Stations, Printers
24	Rated Current	By Vendor
25	Power Factor Range	0.7-1 Lag & Lead
26	Grounding System	Solidly
AC INPUT		
27	Voltage & Variation	<input type="checkbox"/> 380V <input checked="" type="checkbox"/> 400V <input type="checkbox"/> 440V ±15% 3 phase, 4 wire
28	Frequency & Variation	<input checked="" type="checkbox"/> 50 Hz ± 5 % <input type="checkbox"/> 60 Hz ± 5 %
29	Grounding System	Solidly
30	Short Circuit Current on System	50 KA, 1 Sec
31	Short Circuit Capability	> 200 %
32	Rated Input Current	By Vendor
33	THDi for Input Current	<input type="checkbox"/> < 5% <input checked="" type="checkbox"/> <10% <input type="checkbox"/> <15%
34	Input Power Factor (Lag)	<input type="checkbox"/> >0,7 <input type="checkbox"/> >0.8 <input checked="" type="checkbox"/> >0.85 <input type="checkbox"/> >0.9
Charger		
35	Rated Current (A)	By Vendor
36	Rated Input Voltage	<input type="checkbox"/> 380V <input checked="" type="checkbox"/> 400V <input type="checkbox"/> 440V ± 15% 3 phase 4 wire
37	Rated output Voltage	110 VDC(shall be finalized by vendor)
38	No. Of Charger	<input type="checkbox"/> 1 Set(100%) <input checked="" type="checkbox"/> 2 Set(100%)

Vgi



NIOC DATA SHEET FOR RO-UPS

39	Type of Rectifier	Constant voltage current limiting static type thyristor controlled Rectifier(6 Pulses)
40	Voltage Ripple (rms)	± 1% of nominal voltage
41	Voltage Regulation	± 1%
44	Allowable Voltage Range	By Vendor
45	Normal Float Charge Voltage	By Vendor
46	Max Boost Charge Voltage	By Vendor
47	Efficiency	By Vendor
48	Maximum Heat Dissipation	By Vendor
<b>Battery</b>		
49	Type of Batteries (IEC60623)	Sealed Lead Acid Long Life
50	Capacity of battery bank (AH)	By Vendor
51	Backup Time	<input checked="" type="checkbox"/> 30min <input type="checkbox"/> 1hr <input type="checkbox"/> 2hr
52	Country of Origin/Company	Europe, Japan, Korea
53	Date of Manufacture	By Vendor
54	Battery internal resistance	By Vendor
55	No's Of Battery Cells For Each Bank	By Vendor
56	Battery house	<input checked="" type="checkbox"/> Cabinet <input type="checkbox"/> Rack
57	Type of Battery rack/cabinet	Wooden or plastic/epoxy coated steel
58	No's. Of Battery Bank (100%)	<input type="checkbox"/> 1 Set <input checked="" type="checkbox"/> 2 Set half rated
59	Re-charging time to 90% Rated Capacity	8 Hours
60	Battery nominal Voltage per cell	2v
61	Battery final voltage per cell	<input type="checkbox"/> 1V/Cell <input type="checkbox"/> 1,05V/Cell <input type="checkbox"/> 1.1V/Cell <input type="checkbox"/> 1.14V/cell
<b>Inverter</b>		
62	Power Rating	10 KVA
63	Output Voltage	<input checked="" type="checkbox"/> 110Vac <input type="checkbox"/> 230Vac <input checked="" type="checkbox"/> Single Phase <input type="checkbox"/> 3 Phase
64	Output Voltage Regulation	± 1% in steady state
65	Output Voltage Unbalance(At 100% Unbalanced Load)	< 2%
66	Output Frequency & Variation	<input checked="" type="checkbox"/> 50 Hz ± 1% <input type="checkbox"/> 60 Hz ± 1%
67	Output Frequency Regulation	± 1% in steady state
68	Maximum V. Harmonic Distortions (THD%)	Max. 5%(for linear & nonlinear loads)
69	Rated Output Current (Amp)	By Vendor
70	No. of Inverter (100%)	<input type="checkbox"/> 1 Set <input checked="" type="checkbox"/> 2 Set (parallel) <input type="checkbox"/> 3 Set <input type="checkbox"/> 4 Set
71	Type Of Inverter (True Online Double Conversion Technology and pure Sine Wave )	IGBT Technology
72	Galvanic Isolation (Input / Output)	Required
73	Fast Fuse Protection For IGBT Bridge	Required
74	Max. Allowable Current	By Vendor
75	Efficiency (Min)	> 90 %
76	Maximum Heat Dissipation	By Vendor
77	Type of Frequency Synchronizer	By Vendor
78	Crest Factor	Min 3:1
<b>Bypass Isolating Transformer</b>		
79	Type	Double wound dry type air cooled
80	Input / output voltage	Input: <input type="checkbox"/> 380Vac <input checked="" type="checkbox"/> 400Vac <input type="checkbox"/> 440Vac Output: <input checked="" type="checkbox"/> 110Vac <input type="checkbox"/> 230Vac    f=50Hz
81	Bypass transformer KVA rating	10 KVA
82	Short Circuit Impedance	Less than 4%
83	Stabilizer (Servo Control With Galvanic Isolation)	<input checked="" type="checkbox"/> Not Required <input type="checkbox"/> Required
84	Stabilizer Short Circuit Capacity	
85	Stabilizer Static output voltage tolerance	
86	Stabilizer Short Circuit Impedance	



NOC DATA SHEET FOR AC-UPS

87	Stabilizer Phase shift from input to output		
<b>Inverter/ Mains Static Switch</b>			
88	Inverter Switch Type	<input checked="" type="checkbox"/> Thyristor (S.C.R) <input type="checkbox"/> Other	
89	Inverter Rated Current (Continuous)	<input checked="" type="checkbox"/> ≥105% Of Rated Output Current of UPS ≥200% Of Rated Output Current of UPS	
90	Inverter Over Load Capability on Static Switch	>200 % For 100ms >150 % For 1Min >125 % For 10Min	
91	Transfer the inverter output voltage	below 90% of the nominal output voltage exceeds 110% of the nominal output voltage	
92	Re-transfer of the load from the static bypass to the inverter	The inverter output voltage is within ± 5% of the nominal output voltage for more than 3 seconds.	
93	Inverter/Mains Switching Transfer Time(ms)	1/5 Period Of a Cycle	
94	Mains Switch Type	<input checked="" type="checkbox"/> Thyristor (S.C.R) <input type="checkbox"/> Other	
95	Mains Rated Current (Continuous)	200% Of Rated Output Current of UPS	
96	Mains Over Load Capability on Static Switch	>1000 % For 100ms >150 % For 1Min >125 % For 10Min	
97	Fast Fuse Protection For Mains Static Switch	Required	
98	Electronic Change Over Between Mains and inverter	Manual /Automatic	
99	All UPS units shall comply with the requirements for EMC as defined in IEC 62040-2		
100	An earth bar, with a suitable number of earthing bolts or screws, shall be provided.		
<b>Manual Bypass Switch</b>			
101	Rated Current	110% Rated output current of UPS	
102	Maintenance Bypass (Make Before Break)	Required	
103	Over Load Capability	> 1000 % For 100ms	
104	Allowable Over Current (1 Sec)	By Vendor	
<b>AC Distribution Board</b>			
105	Protection Degree	IP31	
106	Feeder quantity	4 * 16 A MCB	
107	Incoming type (IEC 60947)	MCCB, (Shall be finalized by vendor)	
<b>Accessories And Protection</b>			
108			
109	Incoming Cable	NOT Required	
110	Cable Type	NOT Required	
111	Earth Bar	NOT Required	
112	Cable Entry and Accessories	NOT Required	
113	Current Limiting Device Setting	NOT Required	
<b>Alarms</b>			
114		<input checked="" type="checkbox"/> AC input supply failure	
115		<input checked="" type="checkbox"/> Rectifier failure	
116		<input checked="" type="checkbox"/> DC voltage low/high	
117		<input checked="" type="checkbox"/> DC earth fault	
118		<input checked="" type="checkbox"/> Battery discharging	
119		<input checked="" type="checkbox"/> Battery disconnected	
120		<input checked="" type="checkbox"/> Inverter failure	
121		<input checked="" type="checkbox"/> Inverter over loaded	
122		<input checked="" type="checkbox"/> Inverter over temperature	
123		<input checked="" type="checkbox"/> AC output voltage low/high	
124		<input checked="" type="checkbox"/> Output frequency low/high	
125		<input checked="" type="checkbox"/> Ventilation failure & high temp	



# NIDC DATA SHEET FOR AC-UPS

Metering Device			
126		<input checked="" type="checkbox"/> DC/AC Ammeter	
127		<input checked="" type="checkbox"/> DC/AC Voltmeter	
128		<input checked="" type="checkbox"/> Bypass/inverter/Load Frequency Meter	
129	Remote Signals		Required
130	Serial Communication Capability	<input checked="" type="checkbox"/> RS 232 <input type="checkbox"/> RS 485	
131	Fixing Bolt & nuts		Required
132	Lifting lug		Required
133	On-load break switch-fuse For Batteries		Required
Tests ( FAT and SAT shall be performed By the Vendor)			
134	Visual Inspection & Dimensional Check		Required
135	Performance and Function Test		Required
136	Sequence , Operation and Logic Test		Required
137	Dielectric Strength Test		Required
138	Output Voltage Wave Form and THD% Check		Required
139	Charger Voltage Adjustment Test		Required
140	Transfer Time Test		Required
141	Output Regulation / Adjustments Test		Required
142	Alarms Check		Required
143	Autonomy Test		Required
144	Overload /Short Circuit Test		Required
145	Short Circuit test		Required
Note1:	Other Tests shall be performed in Accordance with IEC80146 & IEC62040-3		
Note2:	The Accuracy of all meters shall be better than 1.5%		
Accessories And Special Tools			
146	MIMIC Diagram With LED To Show Operation Condition		Required
147	Hardware and Software for Communication Programming or Setting the CPU or MPU Boards,		Required
148	Automatic battery test and failure alarm		Required
149	Hot and Cold standby unlimited systems		Required
150	IGBT technology		Required
151	Low noise and heat rejection		Required
152	The UPS shall be provided with a standard RS232 or RS485 connection facility. Where specified by the Principal, it shall be also possible to connect the UPS, via either a RS485 or fiber optic link to a DCS or SCADA system for selected analogue and digital data to be made available to a higher level controller. The communication shall function utilizing standard MODBUS protocol (master/slave).		Required
SNMP	Interface for remote monitoring and control via PC		Required
PBM	Progress Battery Management(PBM) with temperature compensation		Not Required
APM	Advanced Power Management(APM) - automated auto start of systems connected as a single system(APM) with an increase in load. Any combination of parallel, hot or cold standby		Required
EPO	Emergency power off		Required